

ATTACHMENT "A"
List of Conditions for CUP17-00001

Approval Date: August 10, 2017
Effective Date: August 22, 2017
Expiration Date: August 22, 2020

This list of conditions applies to: Consideration of a Conditional Use Permit to construct a private school (grades K to 8th) on 15 gross acres within the NC and OP Zones of the Main Street and Freeway Corridor Specific Plan located on the southeast corner of Mariposa Road and Eucalyptus Street (Applicant: Pathways to College; APNs: 0405-042-59 & 60)

The use shall not be established until all conditions of this land use approval application have been met. This approved land use shall become null and void if all conditions have not been completed by the expiration date noted above. Extensions of time may be granted upon submittal of the required application and fee prior to the expiration date.

(Note: the "COMPLETED" and "COMPLIED BY" spaces are for internal City use only).

CONDITIONS REQUIRED AS PART OF SUBMITTAL OF PUBLIC IMPROVEMENT PLANS

<u>COMPLETED</u>	<u>COMPLIED BY</u>
NOT IN COMPLIANCE	MYEAGER

DRAINAGE STUDY. The Developer shall submit three (3) copies of a Final Drainage Study which analyzes the pre-project and proposed project hydrology, including flows from offsite, flows generated onsite, hydraulic properties of flows entering or exiting the project to and from natural or constructed conveyances, and capacity and function of any runoff management structures such as catch basins, inlets, outlets and detention or retention structures. The study must include all information specified in the Citys hydrology study outline

<u>COMPLETED</u>	<u>COMPLIED BY</u>
NOT IN COMPLIANCE	MYEAGER

PERCOLATION TEST. The applicant shall provide percolation test data which are adequate to substantiate the hydrologic performance of all proposed basins, underground retention systems, drywells, or other features requiring percolation of surface water:

- A. Projects shall provide site-specific percolation test data to substantiate the performance and effective drawdown time of all proposed surface retention basins.
- B. Projects shall provide site-specific, depth-appropriate percolation test data for the proposed subsurface infiltration/retention system; and/or for any proposed drywells.
- C. Percolations tests shall be performed in accordance with the procedures in Appendix A of the Riverside County Design Handbook for Low Impact Development Best Management Practices; available online at:

<http://www.floodcontrol.co.riverside.ca.us/NPDES/LIDBMP.aspx>

<u>COMPLETED</u>	<u>COMPLIED BY</u>
NOT IN COMPLIANCE	MMCKINLEY

TRAFFIC STUDY. The applicant shall be required to provide a traffic study prepared by a California licensed traffic engineer. (E)

<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY	GEOTECHNICAL REPORT. The Developer shall provide two copies of the soils report to substantiate all grading building and public improvement plans. Include R value testing and pavement recommendations for public streets. (E B)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY	TITLE REPORT. The Developer shall provide a complete title report 90 days or newer from the date of submittal. (E)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY	UTILITY NON INTERFERE/QUITCLAIM DOCS. The Developer shall provide non interference and or quitclaim letter(s) from any applicable utility agencies for any utility easements that affect the proposed project. All documents shall be subject to review and approval by the Engineering Department and the affected utility agencies. The improvement plans will not be accepted without the required documents and approval from the affected agencies. (E)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY	PLAN CHECK FEES. Plan checking fees must be paid in conjunction with the improvement plan submittal. All required plans, maps, requested studies, CFD annexations, etc. must be submitted as a package. The Developer shall coordinate with the Citys Engineering Analyst, Jamie Carone at (760)947-1149 or jcarone@cityofhesperia.us, to obtain the fee calculation form which shall be completed and submitted, along with fee payment, at time of plan submittal. Any outstanding fees must be paid before final inspection and the release of bonds. (E)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY	IRREVOCABLE OFFERS OF DEDICATION. The Developer shall submit an Offer of Dedication to the Citys Engineering Department for review and approval. At time of submittal the developer shall complete the Citys application for document review and pay all applicable fees. (E)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	CONSTRUCTION PLANS. Five complete sets of construction plans prepared and wet stamped by a California licensed Civil or Structural Engineer or Architect shall be submitted to the Building Division with the required application fees for review. (B)
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	INDEMNIFICATION. As a further condition of approval, the Applicant agrees to and shall indemnify, defend, and hold the City and its officials, officers, employees, agents, servants, and contractors harmless from and against any claim, action or proceeding (whether legal or administrative), arbitration, mediation, or alternative dispute resolution process), order, or judgment and from and against any liability, loss, damage, or costs and expenses (including, but not limited to, attorney's fees, expert fees, and court costs), which arise out of, or are in any way related to, the approval issued by the City (whether by the City Council, the Planning Commission, or other City reviewing authority), and/or any acts and omissions of the Applicant or its employees, agents, and contractors, in utilizing the approval or otherwise carrying out and performing work on Applicants project. This provision shall not apply to the sole negligence, active negligence, or willful misconduct of the City, or its officials, officers, employees, agents, and contractors.

The Applicant shall defend the City with counsel reasonably acceptable to the City. The City's election to defend itself, whether at the cost of the Applicant or at the City's own cost, shall not relieve or release the Applicant from any of its obligations under this Condition. (P)

CONDITIONS REQUIRED PRIOR TO GROUND DISTURBING ACTIVITY

<u>COMPLETED</u>	<u>COMPLIED BY</u>
NOT IN COMPLIANCE	MYEAGER

DRYWELLS. The Project may be permitted to install drywells to ensure the required drawdown time will be achieved.

A. Drywells shall have a City-approved pretreatment component equivalent to a 2-phase system with debris shield and filter element.

B. Drywells shall be constructed by a contractor qualified in the construction of drywells.

C. Drywells in retention basins shall include a secured grate to prevent unauthorized removal.

D. The excavation for the drywell shall penetrate a minimum of 10 continuous feet into a suitable permeable layer or when a depth of 60 feet has been reached, unless otherwise approved by the City Engineer.

E. Drywells that cease to drain a basin or underground system within 72 hours of the end of a storm event shall be replaced or refurbished by the owner. This requirement shall be written in the CC&Rs for all subdivisions where drywells are installed.

F. Drywell usage shall comply with all prevailing City, State, and Federal requirements, including the Underground Injection Control Regulations for Class V Injection Wells.

G. A Drywell Maintenance Plan shall be submitted to the City for review and approval prior to the approval of a drywell installation at a project site.

H. The Drywell Maintenance Plan shall include the following:

1. Drywell(s) location, depth, type, installing contractor, date of installation, owner, maintenance contractor, and emergency contact.

2. Settling chambers and interceptors to be inspected annually;

3. Removal of sediment and debris when:

- a. Sediment/debris level fills = 25% of the capacity;

- b. Drywell ownership or maintenance responsibility changes;

- c. Material not resulting from stormwater/urban runoff enters the settling chamber or interceptor

I. Submit inspection/maintenance reports to the City (Building and Safety) within 10 days of inspection/maintenance.

<u>COMPLETED</u>	<u>COMPLIED BY</u>
NOT IN COMPLIANCE	MYEAGER

FINAL WQMP SUBMITTAL. Submit a final WQMP, prepared using the applicable City of Hesperia WQMP Template, which includes all required or proposed revisions, addresses any comments provided on the draft WQMP, provides final designs for best management practices (BMP's), and includes calculations for BMP sizing. The WQMP must include a final Maintenance Agreement and must be signed and certified by the owner and preparer.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

NPDES. The Project shall enroll under the prevailing National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities issued by the California State Water Resources Control Board and pay applicable fees. The Project shall provide proof of such permit coverage including a copy of the Notice Of Intent Receipt Letter and the project WDID No. to the City.

Alternatively, projects from 1 to 5 acres with an approved Rainfall Erosivity Waiver authorized by U.S. EPA Phase II regulations certifying to the State Water Resources Control Board that construction activity will occur only when the Rainfall Erosivity Factor is less than 5 (R in the Revised Universal Soil Loss Equation), shall provide a copy of the projects Erosivity Waiver Certification and Waiver ID to the City. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

OFFSITE DRAINAGE IMPACT PREVENTION. The Project shall provide safe conveyance for offsite runoff either routed through the project or around the project site. The Project shall ensure that the proposed conveyance of offsite flows will not increase adverse impacts to downstream properties and/or drainage facilities for the 24-hour design storm for 2-year, 10-year, 25-year, and 100-year return frequency rainfall events.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

ONSITE DRAINAGE IMPACT PREVENTION. The Project shall be designed to prevent adverse impacts to downstream properties and/or drainage facilities caused or exacerbated by the project. The project shall demonstrate that runoff from the completed project site will not exceed 90% of the pre-project runoff discharge rates for the 24-hour design storm for 2-year, 10-year, 25-year, and 100-year return frequency rainfall events.

- A. Drawdown Time. All drainage facilities which are designed to percolate/infiltrate surface runoff (including basins, drywells, infiltration trenches, or infiltration-based low impact development features) shall not accumulate standing water for more than 72 hours. All drainage facilities designed to provide detention storage shall recover 100 percent of their design detention volume within 24 hours.
- B. Groundwater Protection. The Project shall ensure any retention/infiltration or detention facilities will not adversely impact groundwater.
- C. Underground Retention/Detention Systems. The Project shall demonstrate a minimum functional life span of 50 years for materials (e.g., polymer, metal, mineral-based, or other) used in underground retention/detention systems.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

OVERFLOW-OUTFALL. Each project shall be designed such that the outfall(s) for discharges from the project site in excess of design capacity and or in excess of the 100-year, 24-hr design storm is are routed to a public street, storm drain,

drainage channel, or natural watercourse.

If such an outfall does not exist, the Project shall provide an outfall.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

STORM WATER POLLUTION PREVENTION PLAN. The Project shall submit to the City for approval two (2) copies of a Storm Water Pollution Prevention Plan (SWPPP) as specified in the prevailing National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities issued by the California State Water Resources Control Board. Prepare the SWPPP using or following the format of the most recent SWPPP Template in the Construction BMP Handbook prepared by the California Stormwater Quality Association (requires subscription); see: <https://www.casqa.org/resources/bmp-handbooks>

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

SWPPP IMPLEMENTATION. All of the requirements of the City-approved Storm Water Pollution Prevention Plan shall be implemented prior to the City's issuance of a grading permit, and shall be maintained until construction is complete and all disturbed areas are fully stabilized. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

APPROVAL OF IMPROVEMENT PLANS. All required improvement plans shall be prepared by a registered Civil Engineer per City standards and per the City's improvement plan checklist to the satisfaction of the City Engineer. Five sets of improvement plans shall be submitted to the Development Services Department and Engineering Department for plan review with the required plan checking fees. All Public Works plans shall be submitted as a complete set. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

DEDICATION(S). The Developer shall grant to the City an Irrevocable Offer of Dedication for Mariposa Road and Eucalyptus Street. The right of way full width for Mariposa Road and Eucalyptus Street shall be per the adopted Hesperia Traffic Circulation Plan and Recommended Intersection Lane Geometry. The Developer shall also grant to the City an Irrevocable Offer of Dedication for any part of the Path of Travel located behind any commercial drive approaches that encroach onto private property. It is the Developer's responsibility to obtain any additional Right of Way dedication needed to satisfy any acceleration / deceleration taper requirements at no cost to the City. Corner cut off right of way dedication per City standards is required at all intersections. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

UTILITY NON INTERFERE/QUITCLAIM DOCS. The Developer shall provide non-interference and or quitclaim letter(s) from any applicable utility agencies for any utility easements that affect the proposed project. All documents shall be subject to review and approval by the Engineering Department and the affected utility agencies. Grading permits will not be issued until the required documents are reviewed and approved by all applicable agencies. Any fees associated with the required documents are the Developer's responsibility. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

GRADING PLAN. The Developer shall submit a Grading Plan with existing contours tied to an acceptable City of Hesperia benchmark. The grading plan shall indicate building footprints and proposed development of the retention basin(s) as a minimum. Site grading and building pad preparation shall include recommendations provided per the Preliminary Soils Investigation. All proposed walls shall be indicated on the grading plans showing top of wall (tw) and top of footing (tf) elevations along with finish grade (fg) elevations. Wall height from finish grade (fg) to top of wall (tw) shall not exceed 6.0 feet in height. Grading Plans are subject to a full review by the City of Hesperia and the City Engineer upon submittal of the Improvement Plans. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

TRAFFIC SIGNAL(S). The Developer shall contribute their fair share for the future construction of the signalized intersection at Mariposa Road and Eucalyptus Street as per approved Traffic Study and City Engineer. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

STREET IMPROVEMENTS. The Developer shall design street improvements in accordance with City standards and these conditions. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MMCKINLEY

MARIPOSA ROAD: Saw-cut (2-foot min.) and match-up asphalt pavement on Mariposa Road across the project frontage, based on City's 120' Major Arterial Roadway Standard and Recommended Intersection Lane Geometry. The curb face will be placed per the Major Arterial Roadway Standard and the Recommended Intersection Lane Geometry. The design shall be based upon an acceptable centerline profile extending a minimum of three hundred (300) feet beyond the project boundaries where applicable. These improvements shall consist of:

- A. 8" Curb and Gutter per City standards.
- B. Sidewalk (width = 6 feet) per City standards.
- C. Roadway drainage device(s).
- D. Streetlights per City standards.
- E. Intersection improvements including handicapped ramps per City standards.
- F. Commercial driveway approaches per City standards.
- G. Pavement transitions per City Standards.
- H. Design roadway sections per existing, approved street sections and per "R" value testing with a traffic index of 12 and per the soils report.
- I. Cross sections every 50-feet per City standards.
- J. Traffic control signs and devices as required by the traffic study and/or the City Engineer.
- K. Provide a signage and striping plan per City standards.
- L. It is the Developer's responsibility to obtain any off-site dedications for transition tapers including acceleration / deceleration tapers per City standards. It is also the Developer's responsibility to obtain any additional Right-of-Way dedication needed to satisfy the 26' minimum paving requirement at no cost to the City.
- M. Relocate existing utilities as required. The Developer shall coordinate with affected utility companies.

<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY
--	--

EUCALYPTUS STREET: Saw-cut (2-foot min.) and match-up asphalt pavement on Eucalyptus Street across the project frontage, based on City's 120' Major Arterial Roadway Standard and Recommended Intersection Lane Geometry. The curb face will be placed per the Major Arterial Roadway Standard and the Recommended Intersection Lane Geometry. The design shall be based upon an acceptable centerline profile extending a minimum of three hundred (300) feet beyond the project boundaries where applicable. These improvements shall consist of:

- A. 8" Curb and Gutter per City standards.
- B. Sidewalk (width = 6 feet) per City standards.
- C. Roadway drainage device(s).
- D. Streetlights per City standards.
- E. Intersection improvements including handicapped ramps per City standards.
- F. Commercial driveway approaches per City standards.
- G. Pavement transitions per City Standards.
- H. Design roadway sections per existing, approved street sections and per "R" value testing with a traffic index of 12 and per the soils report.
- I. Cross sections every 50-feet per City standards.
- J. Traffic control signs and devices as required by the traffic study and/or the City Engineer.
- K. Provide a signage and striping plan per City standards.
- L. It is the Developer's responsibility to obtain any off-site dedications for transition tapers including acceleration / deceleration tapers per City standards. It is also the Developer's responsibility to obtain any additional Right-of-Way dedication needed to satisfy the 26' minimum paving requirement at no cost to the City.
- M. Relocate existing utilities as required. The Developer shall coordinate with affected utility companies.

<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u> MMCKINLEY
--	--

UTILITY PLAN. Utility Plan. The Developer shall design a Utility Plan for service connections and / or private hydrant and sewer connections. Any existing water, sewer, or storm drain infrastructures that are affected by the proposed development shall be removed / replaced or relocated and shall be constructed per City standards at the Developer's expense. (E)

- A. A remote read automatic meter reader shall be added on all meter connections as approved by the City Engineer.
- B. The Developer shall design a Utility Plan for service connections and / or private water and sewer connections. Domestic and fire connections shall be made from the existing 12" PVC water line in Mariposa Road per City Standards.
- C. It is the Developer's responsibility to connect to sewer and pay the appropriate fees. The Developer will be required to connect to the existing 15" PVC sewer main in Mariposa Road per City standards.
- D. Complete V.V.W.R.A.'s "Wastewater Questionnaire for Commercial / Industrial Establishments" and submit to the Engineering Department. Complete the "Certification Statement for Photographic and X-ray Processing Facilities"

as required.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

PRE-CONSTRUCTION MEETING. Pre-construction meetings shall be held between the City the Developer grading contractors and special inspectors to discuss permit requirements monitoring and other applicable environmental mitigation measures required prior to ground disturbance and prior to development of improvements within the public right-of-way. (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

SURVEY. The Developer shall provide a legal survey of the property. All property corners shall be staked and the property address posted. (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

DESIGN FOR REQUIRED IMPROVEMENTS. Improvement plans for off-site and on-site improvements shall be consistent with the plans approved as part of this site plan review application. (E, P)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

CULTURAL RESOURCES. If cultural resources are found during grading, then grading activities shall cease and the applicant shall contract with a City approved archaeologist or paleontologist to monitor grading prior to resuming grading. All cultural resources discovered shall be handled in accordance with state and federal law. A report of all resources discovered as well as the actions taken shall be provided to the City prior to issuance of a Certificate of Occupancy. (P)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

FISH AND GAME FEE. The applicant shall submit a check to the City in the amount of \$2,266.25 payable to the Clerk of the Board of Supervisors of San Bernardino County to enable the filing of a Notice of Determination. (P)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

PRE-CONSTRUCTION SURVEY. A pre-construction survey for the burrowing owl shall be conducted by a City approved and licensed biologist, no more than 30 days prior to ground disturbance. (P)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

PROTECTED PLANTS. Three copies of a protected plant plan shall be submitted to the Building Division showing the present location and proposed treatment of all smoke tree, species in the Agavaceae family, mesquite, large creosote bushes, Joshua Trees, and other plants protected by the State Desert Native Plant Act. The grading plan shall be consistent with the approved protected plant plan. No clearing or grading shall commence until the protected plant plan is approved and the site is inspected and approved for clearing. (P)

CONDITIONS REQUIRED PRIOR TO BUILDING PERMIT ISSUANCE

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

COMBUSTIBLE PROTECTION. Prior to combustibles being placed on the project site an approved all weather fire apparatus access surface and operable fire hydrants with acceptable fire flow shall be installed. The topcoat of asphalt does not have to be installed until final inspection and occupancy. [F 44]

<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE ACCESS 150+ FT. Dead End roadways exceeding one hundred fifty (150) feet in length shall be approved by the Fire Department. [F 45]
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE ACCESS-POINTS OF VEH. ACCESS. The development shall have a minimum of four points of vehicular access. These are for fire/emergency equipment access and for evacuation routes.
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE ACCESS-SINGLE STORY ROAD ACCESS. Single Story Road Access Width. All buildings shall have access provided by approved roads, alleys and private drives with a minimum twenty six (26) foot unobstructed width and vertically to fourteen (14) feet six (6) inches in height. Other recognized standards may be more restrictive by requiring wider access provisions.
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE FLOW TEST. Your submittal did not include a flow test report to establish whether the public water supply is capable of meeting your project fire flow demand. You will be required to produce a current flow test report from your water purveyor demonstrating that the fire flow demand is satisfied. This requirement shall be completed prior to combination inspection by Building and Safety. [F 5b]
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE SURFACE. Fire apparatus access roads shall be designed and maintained to support the imposed loads of fire apparatus and shall be surfaced so as to provide all weather driving capabilities. Road surface shall meet the approval of the Fire Chief prior to installation. All roads shall be designed to 85 compaction and or paving and hold the weight of Fire Apparatus at a minimum of 80K pounds. [F 42]
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	FIRE TURNAROUND. An approved turnaround shall be provided at the end of each roadway one hundred and fifty (150) feet or more in length. Cul de sac length shall not exceed six hundred (600) feet; all roadways shall not exceed a 12 % grade and have a minimum of forty (40) foot radius for residential turns and forty five (45) for non residential turns. [F 43]
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	WATER SYSTEM. Prior to any land disturbance, the water systems shall be designed to meet the required fire flow for this development and shall be approved by the Fire Department. The required fire flow shall be determined by using California Fire Code. The Fire Flow for this project shall be: 7,250 GPM for a four hour duration at 20 psi residual operating pressure. Fire Flow is based on a 70,497 sq.ft. structure. [F 5]
<u>COMPLETED</u> NOT IN COMPLIANCE	<u>COMPLIED BY</u>	WATER SYSTEM COMMERCIAL. A water system approved by the Fire Department is required. The system shall be operational prior to any combustibles being stored on the site. Fire hydrants shall be spaced no more than three hundred (300) feet apart (as measured along vehicular travel ways) and no more than three hundred (300) feet from any portion of a structure. [F 54]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

AQMD APPROVAL. The Developer shall provide evidence of acceptance by the Mojave Desert Air Quality Management District. (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

CONSTRUCTION WASTE. The developer or builder shall contract with the City's franchised solid waste hauler to provide bins and haul waste from the proposed development. At any time during construction, should services be discontinued, the franchise will notify the City and all building permits will be suspended until service is reestablished. The construction site shall be maintained and all trash and debris contained in a method consistent with the requirements specified in Hesperia Municipal Code Chapter 15.12. All construction debris, including green waste, shall be recycled at Advance Disposal and receipts for solid waste disposal shall be provided prior to final approval of any permit. (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

DEVELOPMENT FEES. The Developer shall pay required development fees as follows:

A. School Fees (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

LANDSCAPE PLANS. The Developer shall submit three sets of landscape and irrigation plans including water budget calculations, required application fees, and completed landscape packet to the Building Division. Plans shall utilize xeriscape landscaping techniques in conformance with the Landscaping Ordinance. The number, size, type and configuration of plants approved by the City shall be maintained in accordance with the Development Code. (P)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

LIGHT AND LANDSCAPE DISTRICT ANNEXATION. Developer shall annex property into the lighting and landscape district administered by the Hesperia Recreation and Parks District. The required forms are available from the Building Division and once completed, shall be submitted to the Building Division. (RPD)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

SOLID MASONRY WALLS AND FENCES. The Developer shall submit four sets of masonry wall/wrought iron fencing plans to the Building Division with the required application fees for all proposed walls. A combination solid three foot high split face masonry wall or other approved decorative wall with a three foot high wrought iron fence shall be provided along the property lines where headlight glare from vehicles on site would negatively affect adjacent residentially designated properties. An approved six foot high wall with decorative cap may be substituted for the combination wall/fence provided its height is in accordance with the Development Code. (P)

CONDITIONS REQUIRED PRIOR TO CERTIFICATE OF OCCUPANCY

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

EXECUTED AND RECORDED WQMP MAINTENANCE AGREEMENT. The WQMP Maintenance Agreement: Covenant and Agreement Regarding Water Quality Management Plan and Stormwater Best Management Practices Transfer, Access, and Maintenance, must be (1)

prepared using the WQMP Maintenance Agreement Template provided as Attachment A to the City of Hesperia WQMP Templates and (2) fully executed and recorded with the San Bernardino County Assessor-Recorder-County Clerk's office. A copy of the recorded WQMP Maintenance Agreement must be received before the City will issue a Certificate of Occupancy.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

VOLUME CERTIFICATION. The property owner will provide the City with certified as-built dimensions of the basins and the actual volume of storage provided. This must be based on As-Built topographic surveys made by either a Civil Engineer or Land Surveyor who is registered to practice in California. These as-built volumes must reflect permanent conditions, with finished landscaping in place. The volumes shall be certified by the Design Engineer that the volumes provided meet or exceed the required design volumes per City requirements and the approved Water Quality Management Plan. The volume of storage provided must equal or exceed the approved design volumes before the City will issue Letters of Acceptance for maintenance of any public facilities.

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

AS BUILT PLANS. The Developer shall provide as built plans. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

ELECTRONIC COPIES. The Developer shall provide electronic copies of the approved project in AutoCAD format Version 2007 to the City's Engineering Department. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

PUBLIC IMPROVEMENTS. All public improvements shall be completed by the Developer and approved by the Engineering Department. Existing public improvements determined to be unsuitable by the City Engineer shall be removed and replaced. (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

FIRE ALARM-AUTO OR MANUAL. A manual, automatic or manual and automatic fire alarm system complying with the California Fire Code, NFPA and all applicable codes is required. The applicant shall hire a Fire Department approved fire alarm contractor. The fire alarm contractor shall submit three (3) sets of detailed plans to the Fire Department for review and approval. The required fees shall be paid at the time of plan submittal. [F 62a]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

FIRE EXTINGUISHERS. Hand portable fire extinguishers are required. The location, type, and cabinet design shall be approved by the Fire Department. [F88]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

FIRE SPRINKLER NFPA#13. An automatic fire sprinkler system complying with NFPA Pamphlet #13 and the Fire Department standards is required. The applicant shall hire a Fire Department approved fire sprinkler contractor. The fire sprinkler contractor shall submit three (3) sets of (minimum 1/8 scale) shall include hydraulic calculations and manufacturers specification sheets. The contractor shall submit plans showing type of storage and use with the applicable protection system. The required fees shall be paid at the time of plan submittal. [F 59]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

HOOD AND DUCT SUPPRESSION. An automatic hood and duct fire extinguishing system is required. A Fire Department approved designer/installer shall submit three (3) sets of detailed plans (minimum 1/8 scale) with manufactures specification sheets to the Fire Department for review and approval. The required fees shall be paid at the time of plan submittal. [F 65]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

HYDRANT MARKING. Blue reflective pavement markers indicating fire hydrant locations shall be installed as specified by the Fire Department. In areas where snow removal occurs or non paved roads exist, the blue reflective hydrant marker shall be posted on an approved post along the side of the road, no more than three (3) feet from the hydrant and at least six (6) feet high above the adjacent road. [F80]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

KNOX BOX. An approved Fire Department key box is required. [F85]

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

DEVELOPMENT FEES. The Developer shall pay required development fees as follows:

- A. Development Impact Fees (B)
- B. Utility Fees (E)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

UTILITY CLEARANCE AND C OF O. The Building Division will provide utility clearances on individual buildings after required permits and inspections and after the issuance of a Certificate of Occupancy on each building. Utility meters shall be permanently labeled. Uses in existing buildings currently served by utilities shall require issuance of a Certificate of Occupancy prior to establishment of the use. (B)

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY

ON SITE IMPROVEMENTS. All on site improvements as recorded in these conditions, and as shown on the approved site plan shall be completed in accordance with all applicable Title 16 requirements. The building shall be designed consistent with the design shown upon the approved materials board and color exterior building elevations identified as Exhibit A. Any exceptions shall be approved by the Director of Development Services. (P)

Others

COMPLETED
NOT IN COMPLIANCE

COMPLIED BY
MYEAGER

NPDES-PERMIT TERMINATION. Upon completion of construction, the Project shall ensure that all disturbed areas are stabilized and all construction waste, equipment, and unnecessary temporary BMPs are removed from the site. In addition, the Project shall file a Notice of Termination (NOT) with the Lahontan Regional Water Board as required by the NPDES General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities, and provide to the City a copy of the approved NOT. (E)

NOTICE TO DEVELOPER: IF YOU NEED ADDITIONAL INFORMATION OR ASSISTANCE REGARDING THESE CONDITIONS, PLEASE CONTACT THE APPROPRIATE DIVISION LISTED BELOW:

(B) Building Division	947-1300
(E) Engineering Division	947-1476
(F) Fire Prevention Division	947-1603
(P) Planning Division	947-1200
(RPD) Hesperia Recreation and Park District	244-5488